

1 / A101 POST AND RAIL DETAIL (N.I.C.)
SCALE: 3/4"=1'-0"
PEDESTRIAN CONTROL DEVICE

NOTES:
1. G.C. IS TO PROVIDE ALL VINYL BASE ON ALL CABINETRY SUPPLIED BY OWNER.
2. ALL REFRIGERATION CASES (& INSTALLATION OF) BY REFRIGERATION CONTRACTOR. ALL UNDER FLOOR PVC TRENCHES, PITS & COVERS, PLUMBING, ELECTRICAL, ROOF TOP PATE CURBS, PIPE CHASE, FROST BREAKS, AND UNDER FLOOR INSUL. PROVIDED BY G.C.
3. G.C. TO PROVIDE A "KNOX BOX" BY THE STORE ENTRANCE. VERIFY LOCATION AND STYLE OF BOX WITH LOCAL FIRE MARSHALL.

EQUIPMENT PLATFORM PLAN
SCALE: 1/8"=1'-0"



FLOOR PLAN
SCALE: 1/8"=1'-0"

BUILDING AREA

ENTRY/CARTS	414 S.F.
WAREHOUSING	2,094 S.F.
EQUIPMENT AREA	146 S.F.
FREZR/COOLER/CASEWORK	2,871 S.F.
STORAGE:	**5,525 S.F.**
USEABLE SALES AREA	6,837 S.F.
CUSTOMER SERVICE	130 S.F.
STORAGE SHELF UNITS	1,440 S.F.
SALES AREA:	**8,407 S.F.**
FOOD PREP:	**480 S.F.**
OFFICE/SERVICE/LOUNGE	**354 S.F.**
TOILET/CORRIDOR	189 S.F.
EXT. WALL AREA	**526 S.F.**
TOTAL BUILDING AREA:	**15,886 S.F.**

WALL KEY

1. 8" LT. WT. MASONRY BLOCK w/ TRUSS TYPE REINF. @ 16" O.C. VERT., BUILD UP TIGHT TO DECK (REFER TO FRAMING PLAN AND FRAMING DETAILS)
2. NON-BEARING 3-5/8", 25 GA. METAL STUDS @ 16" O.C. TO 10'-0" A.F.F. WITH 5/8" GYP. BD. EACH SIDE TO 12" ABOVE CEILING. 20 GA. STUDS AND BLOCKING AT CABINETRY LOCATIONS.
3. FRP ON GYP. BD. OR BLOCK WALL TO ABOVE CEILING.
4. SOUND ATTENUATION BATT INSULATION, FULL HEIGHT TO MATCH WALL THICKNESS.
5. 3-5/8" FURRING, 25 GA. METAL STUDS @ 16" O.C. WITH 5/8" GYP. BD. TO 12" ABOVE CEILING.
6. 3/4" NON-COMBUSTIBLE PLYWOOD IN LIEU OF 5/8" GYP. BD. ON METAL STUDS INSIDE EQUIPMENT ROOM #105.
7. 3/4" NON-COMBUSTIBLE PLYWOOD FASTENED DIRECTLY TO BLOCK WALL UP TO 10'-0" A.F.F.
8. 3-5/8", 18 GA. METAL STUDS @ 16" O.C. TO ROOF DECK. REFER TO SECTIONS FOR WALL FINISH.
9. NON-BEARING, DEFLECTION TRACK, 3-5/8", 18 GA. METAL STUDS @ 16" O.C. TO ROOF DECK WITH 5/8" GYP. BD. EACH SIDE TO 12" ABOVE CEILING ON MISC. ROOMS SIDE, AND TO ROOF DECK ON SIDE EXPOSED TO SALES AREA. REFER TO DETAIL 6/A401, NOTE: FIRST 48" FROM FIN. FLR. TO BE 5/8" HIGH-IMPACT GYP. BD. ON SALES AREA SIDE.
10. NON-BEARING, 3-5/8", 25 GA. METAL STUDS @ 16" O.C. TO ROOF DECK WITH 5/8" GYP. BD. EACH SIDE. FIRST 48" FROM FLR. TO BE 5/8" HIGH-IMPACT GYP. BD. ON SALES SIDE. 3/4" NON-COMBUSTIBLE PLYWOOD FIRST 8' FROM FINISH FLOOR AND 5/8" HIGH IMPACT GYP. BD. ON RECEIVING ROOM SIDE.
11. NON-BEARING 6", 25 GA. METAL STUDS @ 24" O.C. TO 10'-0" A.F.F. w/ 1/2" GYP. BD. ON 1/2" NON-COMBUSTIBLE PLYWOOD ON MANAGER'S OFFICE SIDE & 1/2" NON-COMBUSTIBLE EQUIPMENT ROOM SIDE. REFER TO DETAIL 5/A601.
12. NON-BEARING 3-5/8", 25 GA. METAL STUDS @ 16" O.C. TO 10'-8" A.F.F. WITH 5/8" GYP. BD. EACH SIDE TO 12" ABOVE CEILING, TO TOP OF STUD WALL WHERE NO CLG. EXISTS. FIRST 48" FROM FIN. FLR. TO BE 5/8" HIGH-IMPACT GYP. BD. ON CORRIDOR SIDE.
13. 8" 25 GA. METAL STUDS @ 16" O.C. TO 10'-0" A.F.F. WITH 5/8" GYP. BD. EACH SIDE.
14. 8" MASONRY BLOCK w/ TRUSS TYPE REINF. @ 16" O.C. TO 12'-8" A.F.F.
15. NON-BEARING, DEFLECTION TRACK, 6", 20 GA. METAL STUDS @ 16" O.C. TO ROOF DECK W/ 3/4" NON-COMBUSTIBLE PLYWOOD FIRST 8' FROM FINISH FLOOR AND 5/8" HIGH-IMPACT GYP. BD. TO BELOW DECK ON RECEIVING ROOM 117 SIDE.
16. 3-5/8", 20 GA. METAL STUDS @ 16" O.C. TO 3'-6" ABOVE MTL. GRATE AT EQUIPMENT PLATFORM, COVER OUTSIDE FACE WITH 3/4" NON-COMBUSTIBLE PLYWOOD FASTENED TO STUDS WITH REMOVABLE SCREWS FOR FIRST 3'-6" ABOVE CONC. FLOOR & AT EQUIPMENT PLATFORM. REFER TO SECTION #2/A301.

- INSIDE CORNER TRIM, BY REFRIGERATION CONTRACTOR
- 2" X 2" X 48" HIGH STAINLESS STEEL CORNER GUARD TRIM BY G.C., 12 GA.
- "U" SHAPE 48" HIGH STAINLESS STEEL CORNER GUARD TRIM @ WALL ENDS BY G.C. - 12 GA., w/ 2" SIDE RETURNS
- WINDOW SHADES - REFER TO SPECIFICATIONS

BY OWNER ITEMS

THE FOLLOWING ITEMS WILL BE SUPPLIED AND INSTALLED BY GORDON FOOD SERVICE:

1. SHELVING UNITS.
2. BACKROOM SHELVING. (U.N.O.)
3. DUMPSTER UNITS
4. EXTERIOR WALL MOUNTED SIGNS (CONDUIT & WIRING BY E.C.) (3) THUS
5. COMMUNICATIONS CONDUITS AND BOXES BY E.C. PER SHEET E105, COMMUNICATION WIRING BY OWNER.
6. SHOPPING CARTS (75/10).
7. REFRIGERATION WORK, ALL WIRING PER PLANS BY E.C.
8. ADDRESS NO.'s ON ENTRANCE GLASS

ARCHITECTS • CIVIL ENGINEERS
paradigm design
550 3 MILE N.W.
SUITE B
GRAND RAPIDS, MI 49544
PHONE (616) 785 - 5656
FAX (616) 785 - 5657
WEB ParadigmAE.com

PROJECT

GFS MARKETPLACE

COPLEY TOWNSHIP

TEMP 120 ROTHROCK ROAD
AKRON, OH

BLDG OWNER:

GFS MARKETPLACE REALTY FIVE, LLC

P.O. BOX 1812
GRAND RAPIDS, MI

RELEASE DATE

2-06-12	FOR TOWNSHIP REVIEW
4-23-12	OWNER REVIEW
4-27-12	FOR PERMITS & CONSTRUCTION
5-21-12	FOR PERMITS, BIDS & CONSTRUCTION
5-29-12	ADDENDUM #1
8-15-12	BULLETIN #1

PROJECT 1105054

SHEET A101

Wednesday, July-10-2013 at 9:17am G:\1105054 GFS Copley Township OH- Akron\Drawings\Architectural\A101-1054.dwg elk